

**#WS-18-12 MIRACLES PARK (fka Dewey St. Park) POURED-IN-PLACE PLAYGROUND SAFETY SURFACING (PHASE II) (#5562765)**

**BID DATE: MARCH 7, 2018**

**Seiler Bros.  
Construction Inc**

Item#	Item Description	UofM	Qty	Unit Price	Extension
<b>MIRACLES PARK - POURED-IN-PLACE PLAYGROUND SAFETY SURFACING</b>					
1	F&I func Pourd-In-Place Plygrd Sfty Surf Approx 3,426SFw/Exc,saw/cut ex rubber surf,4"crushed agg base course,4"conc base pavmt,rubber playgrd safty surf,backfill,3"pulv topsoil,seed,fert,hydro&water	LS	1	\$84,915.00	\$84,915.00
2	Furnish & Install Inlet Protection (Type "D")	EA	2	\$60.00	\$120.00
3	Install Surface Mount ADA Wheelchair Swing Platform (Furnished by Others)	EA	1	\$485.00	\$485.00
4	Install Surface Mount Concerto 2-Congas & Concerto Spin Cabasas Medium (Furnished by Others)	LS	1	\$485.00	\$485.00
5	New 6" Concrete Sidewalk Over New 4" C.A.B.C. (w/#4 deformed & epoxy coated rebar)	SF	915	\$6.90	\$6,313.50
6	6" Concrete Sidewalk (Removed & Replaced)	SF	60	\$6.10	\$366.00
7	Sawing Concrete Sidewalk (Full Depth)	LF	20	\$8.00	\$160.00
8	Furnish & Install 4" Dual Wall Perforated Underdrain w/Cap (Wrapped Pipe)	LF	60	\$20.15	\$1,209.00
9	Furnish & Install 3" Screened Topsoil, Seed, Hydromulch & Water	SY	390	\$9.18	\$3,580.20
10	Furnish & Install Cedar Split Rail Fence (2 Rail System)	LF	160	\$8.85	\$1,416.00
<b>BASE BID TOTAL</b>				<b>\$99,049.70</b>	